General Disclaimer

One or more of the Following Statements may affect this Document

- This document has been reproduced from the best copy furnished by the organizational source. It is being released in the interest of making available as much information as possible.
- This document may contain data, which exceeds the sheet parameters. It was furnished in this condition by the organizational source and is the best copy available.
- This document may contain tone-on-tone or color graphs, charts and/or pictures, which have been reproduced in black and white.
- This document is paginated as submitted by the original source.
- Portions of this document are not fully legible due to the historical nature of some
 of the material. However, it is the best reproduction available from the original
 submission.

Produced by the NASA Center for Aerospace Information (CASI)

(NASA-CR-150852) LIBBFY-OWENS-FORD SOLAR COLLECTOR STATIC LOAD TEST (Wyle Labs., Inc.) 6 p HC A02/MF A01 CSCL 10A

N79-13494

Unclas G3/44 39364

DOE/NASA CONTRACTOR REPORT

DOE/NASA CR-150852

LIBBEY-OWENS-FORD SOLAR COLLECTOR STATIC LOAD TEST

Prepared by


Wyle Laboratories Solar Energy Systems Division Huntsville, Alabama 35805

Under subcontract with IBM Corp, Federal Systems Div, Huntsville, Ala. 35805

Contract NAS8-32036

National Aeronautics and Space Administration George C. Marshall Space Flight Center, Alabama 35812

For the U. S. Department of Energy





U.S. Department of Energy



	TECHNICAL REPORT STANDARD TITLE PAGE
1. REPORT NO. DOE/NASA CR-150852 2. GOVERNMENT A	The state of the s
4. TITLE AND SUBTITLE	5. REPORT DATE
Libbey-Owens Ford Solar Collector Static Loa	nd Test December 1978
	6. PERFORMING ORGANIZATION CODE
7. AUTHOR(S)	B. PERFORMING ORGANIZATION REPORT #
9. PERFORMING ORGANIZATION NAME AND ADDRESS	10. WORK UNIT, NO.
Wyle Laboratories	11. CONTRACT OR GRANT NO.
Solar Energy Systems Division	NAS8-32036
Huntsville, Alabama 35805	13. TYPE OF REPORT & PERIOD COVERED
12. SPONSORING AGENCY NAME AND ADDRESS	Contractor Report
National Aeronautics and Space Administratio	
Washington, D. C. 20546	14. SPONSORING AGENCY CODE
Wildington, D. C. 20010	14. SPONSONING AGENCY CODE
15. SUPPLEMENTARY NOTES	
This work was done under the technica	Il management of Mr. Charles N. Thomas,
George C. Marshall Space Flight Center, Ala	bama.
on the Libbey-Owens-Ford Solar Collector and the static load tests were performed evaluation. The thermal performance Libbey-Owens-Ford Solar Collector a CR-150508. The test article is a flat plate solar comedium. The overall dimensions of the content of the collector and the coll	subsequent to the thermal performance evaluation tests and results on the re contained in report, DOE/NASA collector that uses liquid as the heat transfer the collector are 3' x 7' x 4-3/4". The 021" thick. It has a double glass cover
17. KEY WORDS	UC-59c Unclassified-Unlimited UC-59c Unclassified-Unlimited WILLIAM A. BROOKSBANK, JR.
	Mgr. Solar Heating and Cooling Project Office
	ASSIS (At this seem) 21 NO OF PAGES 22 PRICE

Unclassified

Unclassified

5

NTIS

1.0 PURPOSE

The purpose of this document is to present the results of static load tests which were performed on a Libbey-Owens-Ford solar collector. These tests were performed subsequent to the thermal performance evaluations on the subject collector. This report was prepared as an addendum to the previously issued report, DOE/NASA CR-150508, on the Libbey-Owens-Ford collector thermal performance tests.

2.0 SUMMARY

The results of static load tests on the Libbey-Owens-Ford (LOF) solar collector are reported herein. Thermal performance test results on the LOF collector were previously reported in Test Report DOE/NASA CR-150508.

Results of static load tests de onstrated that the LOF collector performed satisfactorily.

3.0 TEST REQUIREMENTS AND PROCEDURES (Continued)

3.1 Collector Load Test

Tested By	G. Ouren
Started	6/27/78
Completed	6/27/78

3.1.1 Requirements

One solar collector shall be subjected to load testing. The specified load requirements are listed in paragraph 5.5.3. The collector shall be mounted as indicated in Figure 1 and shall be oriented such that the glazing is horizontal. Uniform loads shall be applied by means of a transparent flexible diaphragm which can be covered with a uniform layer of transparent liquid of varying depths to obtain the desired load variations. If either breakage or leakage to the collector occurs before all six test steps have been conducted, the load testing shall be discontinued. If it is determined that the failure is the result of a collector which is not representative of the vendor's normal product, the collector shall be replaced and the load test started over. If it is determined that the ultimate load capability of the collector has been reached, the load testing shall be terminated.

3.1.2 Procedure

- 1. Mount the collector in the horizontal plane.
- 2. Place the load frame with liner over the collector.
- 3. Fill the load frame liner with water to a level corresponding to the Step 1 load indicated in paragraph 5.5.3 and let stand for five minutes.
- 4. Drain and remove the load frame.
- Flush the collector exposed surface with water and inspect for leaks.
- If the collector leaked or was damaged due to the load, record and indicate what the load level is.
- If the collector does not leak and is not damaged, record the load level and repeat steps 3 - 5 for the next load level.

3.1.3 Results


The results of this test were tabulated as shown on the following page.

3.0 TEST REQUIREMENTS AND PROCEDURES (Continued)

3.1.3 Results (Continued)

Service Load Steps

Step No.	Load (Lb/Ft ²)	Pass/Fail	Comments.
1	10	Pass	
2	. 20 .	Pass	
3 .	30	Pass	
4	. 50	Pass	
5	80 .	Pass	
6	120 .	Pass	



2 x 6 (Typ.) Mounting Frame

FIGURE 1. Test Setup for Static Loads.

♦U.S. GOVERNMENT PRINTING OFFICE 1978-640-081/355 REGION NO. 4